# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34130

## APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

### Construction of R O Plant at Kodigehalli in Ward No.08

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 24.66 | KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, Page No. 5 / Item No. 2.3/ PWD SR 2018-19 | Cum | 303.22 | 7477.41 | Rupees Three Hundred Three and Twenty Two Paise Only |
| 2 | 5.49 | KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. No. 12/ Item No. 4.3/ PWD SR 2018-19 | Cum | 5174.04 | 28405.48 | Rupees Five Thousand One Hundred Seventy Four and Four Paise Only |
| 3 | 2.7 | KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23 / Item No. 5.6 / PWD SR 2018-19 | Cum | 4660.9 | 12584.43 | Rupees Four Thousand Six Hundred Sixty and Ninety Paise Only |
| 4 | 1.62 | KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23 / Item No. 5.9 / PWD SR 2018-19 | Cum | 5560.42 | 9007.88 | Rupees Five Thousand Five Hundred Sixty and Forty Two Paise Only |
| 5 | 12.6 | KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.115, I.No. 15.1 of PWD SR 2018-19) | Sqm | 142.99 | 1801.67 | Rupees One Hundred Forty Two and Ninety Nine Paise Only |
| 6 | 0.36 | KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.6 of PWD SR 2018-19) | Cum | 5498.56 | 1979.48 | Rupees Five Thousand Four Hundred Ninety Eight and Fifty Six Paise Only |
| 7 | 16.47 | KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification No. KBS 2.9 (P.6/I.2.10) PWD SR 2018-19 | Cum | 203.84 | 3357.24 | Rupees Two Hundred Three and Eighty Four Paise Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 8 | 43.91 | KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4. Page No. 25 / Item No. 5.27.1 / PWD SR 2018-19 | Sqm | 924.88 | 40611.48 | Rupees Nine Hundred Twenty Four and Eighty Eight Paise Only |
| 9 | 8.25 | KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2018-19 | Cum | 5738.91 | 47346.01 | Rupees Five Thousand Seven Hundred Thirty Eight and Ninety One Paise Only |
| 10 | 0.72 | KSRB 4.2.10 : Providing and laying in position reinforced cement concrete ofmix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplastisiser @ 0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, complete as per specification. Specification NO. KBS 4.1, 4.6 Page No. 14 / Item No. 4.19 / PWD SR 2018-19 | Sqm | 446.21 | 321.27 | Rupees Four Hundred Forty Six and Twenty One Paise Only |
| 11 | 1 | KSRB 4.9.1: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 18 / Item No. 4.46.2 / PWD SR 2018-19 - FE 500 | tonne | 71968.04 | 71968.04 | Rupees Seventy One Thousand Nine Hundred Sixty Eight and Four Paise Only |
| 12 | 57.9 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.31/ PWD SR 2018-19 | Sqm | 363.05 | 21020.60 | Rupees Three Hundred Sixty Three and Five Paise Only |
| 13 | 1.08 | KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16 / Item No. 4.37 / PWD SR 2018-19 | Sqm | 327.56 | 353.76 | Rupees Three Hundred Twenty Seven and Fifty Six Paise Only |
| 14 | 8.99 | KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.21 / PWD SR -2018-19 | Sqm | 238.32 | 2142.50 | Rupees Two Hundred Thirty Eight and Thirty Two Paise Only |

Taranath
Signature of the contractor



9/07
Executive Engineer
9/07

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 15 | 27.9 | KSRB 15.3.11 :Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.19 / PWD SR 2018-19 (Inside wall) | Sqm | 274.83 | 7667.76 | Rupees Two Hundred Seventy Four and Eighty Three Paise Only |
| 16 | 36.89 | KSRB 15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (P. 115 / I. 15.33 PWD SR - 2018-19). | Sqm | 32.45 | 1197.08 | Rupees Thirty Two and Forty Five Paise Only |
| 17 | 54.72 | KSRB 15.3.9: Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 114 / Item No. 15.17 / PWD SR 2018-19 (Out side Wall) | Sqm | 248.46 | 13595.73 | Rupees Two Hundred Forty Eight and Forty Six Paise Only |
| 18 | 64.79 | KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications PWD SR 2018-19 (P.117 /Item No 15.49.1) | Sqm | 111.55 | 7227.32 | Rupees One Hundred Eleven and Fifty Five Paise Only |
| 19 | 54.72 | KSRB 15-16.1: providing and finishing external walls in two coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications PWD SR 2018-19 (P. 118 / I. 15.53.2) with Primer | Sqm | 103.44 | 5660.24 | Rupees One Hundred Three and Forty Four Paise Only |
| 20 | 16.08 | KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 121 / Item No. 15.74 / PWD SR 2018-19 | Sqm | 96.34 | 1549.15 | Rupees Ninety Six and Thirty Four Paise Only |
| 21 | 8.99 | Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. Page No. 107 / Item No. 14.43 / PWD SR 2018-19 | Sqm | 1114.52 | 10019.53 | Rupees One Thousand One Hundred Fourteen and Fifty Two Paise Only |
| 22 | 12.76 | KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface ( excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 30x60 cms 6mm thick with border of size 30 x 10 cms. (P.No.108, I.No. 14.41.2 of PWD SR 2018-19) | Sqm | 1655.04 | 21118.31 | Rupees One Thousand Six Hundred Fifty Five and Four Paise Only |
| 23 | 5.4 | Providing and laying/fixing cement base, precast pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring reads of steps of steps and landin, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of material,s including cutting, griding the edge ti half/ful rounf wherever requires labour, curing complete as per specification Page No. 109 / Item No. 14.62 / PWD SR 2018-19 | sqm | 1249.4 | 6746.76 | Rupees One Thousand Two Hundred Forty Nine and Forty Paise Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 24 | 1.08 | KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm thick reeded glass with teakwood beading of required size, all steel section should confirm to I.S. 7452:1990, 4nos, of holdfasts of approved size section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be thoroughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification NO. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 Page No. 32 / Item No. 7.7/ PWD SR 2018-19 | Sqm | 3953.04 | 4269.28 | Rupees Three Thousand Nine Hundred Fifty Three and Four Paise Only |
| 25 | 7.5 | KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete Including pulling hooks, 4nos handles wit hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m Specification NO. KBS 7.10 / 7.12 Page No. 31 / Item No. 7.5/ PWD SR 2018-19 | Sqm | 2643.81 | 19828.58 | Rupees Two Thousand Six Hundred Forty Three and Eighty One Paise Only |

Taranath
Signature of the contractor



9/07
Executive Engineer
09/07

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 26 | 6.3 | KSRB 7.14 : Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grovesection 2.683 kg/m and bottom 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick prelaminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with lower sections, the glass and panels fitted with glazing clips of 19mmx17.3mm. with thickness of 0.9mm. weight 0.124kg/m; aluminium sections pre-treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherence of mortars or any other sticky materials; vertical members embedded in the flooring by making suitable size holes and fixing with cement mortar, with necessary opening for fixing of doors of standard size (excluding cost of door opening) All the frame should be throughly cleaned free from rust, scale or dirt including cost of | Sqm | 4862.71 | 30635.07 | Rupees Four Thousand Eight Hundred Sixty Two and Seventy One Paise Only |
| 27 | 21 | KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWTD SR 2018-19) | Cum | 237.09 | 4978.89 | Rupees Two Hundred Thirty Seven and Nine Paise Only |
| 28 | 14 | KSRRB M400-19: Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407 (P.No155 of I.No.20.20 in PW,P&IWTD SR 2018-19) | Cum | 208.03 | 2912.42 | Rupees Two Hundred Eight and Three Paise Only |
| 29 | 140 | KSRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers,using cement & course sand for manufacture of blocks of approved size ,shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No 103 of I.No.14.6 in PW,P&IWTD SR 2018-19) | Sqm | 1048.09 | 146732.60 | Rupees One Thousand Forty Eight and Nine Paise Only |
| 30 | 622 | Providing and fixing precast solid concrete kerb stones made out of CC. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete (P. No. 27 I. No.5.29.2 in PW,P&IWTD SR 2018-19) | No | 438.94 | 273020.68 | Rupees Four Hundred Thirty Eight and Ninety Four Paise Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 31 | 98 | KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No.180, I.No. 24.1 of PW,P&IWTD SR 2018-19) | Sqm | 79.63 | 7803.74 | Rupees Seventy Nine and Sixty Three Paise Only |
| 32 | 1 | Purpose to dose sodium Bi-carbonate for enhances product water SS till the pre-filteration & SS from HPP to thhe premeter line termination point NRV's pressure relief valves, wherever needed the system will be on common SS base frame supply & manufacture of complete Reverse Osmosis plant stainless steel tank (2kl) Raw water tank (5kl) with stainless steel pipe line required for plant erection. | Sqm | 483585.0 | 483585.00 | Rupees Four Hundred Eighty Three Thousand Five Hundred Eighty Five Only |
| 33 | 2 | Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A (Page No. 05, Item No.2.1 KPWD SR 2014-15 b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch | Point | 230.06 | 460.12 | Rupees Two Hundred Thirty and Six Paise Only |
| 34 | 2 | c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch | Point | 340.86 | 681.72 | Rupees Three Hundred Forty and Eighty Six Paise Only |
| 35 | 12 | Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (Page No. 03, Item No. 1.6) KPWD SR 2014-15 (1.6.5) 4"x4"x3" ( 101x101x76mm) | Each | 63.85 | 766.20 | Rupees Sixty Three and Eighty Five Paise Only |
| 36 | 6 | (1.6.1) 12"x12"x3" (300x300x76mm) | Each | 108.92 | 653.52 | Rupees One Hundred Eight and Ninety Two Paise Only |
| 37 | 6 | (1.6.3)10"x7"x3" (254x178x76mm) | Each | 81.69 | 490.14 | Rupees Eighty One and Sixty Nine Paise Only |
| 38 | 6000 | Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws. (Page No. 17, Item No. 3.9) KPWD SR 2014-15 | Sqm | 0.23 | 1380.00 | and Twenty Three Paise Only |
| 39 | 10 | Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall (Page No. 03, Item No.1.7.1) KPWD SR 2014-15 | Sqm | 19.72 | 197.20 | Rupees Nineteen and Seventy Two Paise Only |
| 40 | 10 | Supplying heavy gauge PVC Conduit Pipe 19/20 mm dia 2 mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. (Page No. 02, Item No. 1.3.1) KPWD SR 2014-15 | Sqm | 52.58 | 525.80 | Rupees Fifty Two and Fifty Eight Paise Only |
| 41 | 2 | Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps. (Page No. 20, Item No. 4.2) KPWD SR 2014-15 | No | 82.63 | 165.26 | Rupees Eighty Two and Sixty Three Paise Only |
| 42 | 4 | Supplying patti type fluorescent tube light fitting of 2' - suitable for 14 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with HF Electronic Ballast , locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC . Supply including T5 lamp. (Page No. 20, Item No. 4.5) KPWD SR 2014-15 | No | 554.95 | 2219.80 | Rupees Five Hundred Fifty Four and Ninety Five Paise Only |

Signature of the contractor



9/07

Executive Engineer

9/07

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K R TARANATH ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 43 | 5 | Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A 1.5 sqmm (Page No. 06, Item No. 2.5.2) KPWD SR 2014-15 | Sqm | 17.47 | 87.35 | Rupees Seventeen and Forty Seven Paise Only |
| 44 | 4 | Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 60/100 watts 230V GLS lamp. (Page No. 20, Item No. 4.3) KPWD SR 2014-15 | No | 701.43 | 2805.72 | Rupees Seven Hundred One and Forty Three Paise Only |
| 45 | 1 | Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia (Page No. 55, Item No. 7.1) KPWD SR 2014-15 | Sqm | 2560.65 | 2560.65 | Rupees Two Thousand Five Hundred Sixty and Sixty Five Paise Only |
| | | | | | 1309918.88 | |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92